

1 090300

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,174 -0000

NE NE SE , SEC. 20 , T 26 S, R 15 W/K

2310 feet from (S) section line

330 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Stratford Well # 1

Operator: Brougner Oil, Inc.

County Pratt 132.44

Name & Address Drawer 1367 - 614 Patton Rd.

Well Total Depth 4075 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 452

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 6 Month: March Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4075' Perfs at 4043-49, 3926-27, 2903-06'

1st plug sand back to 3855' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 120 sx cement.

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 2:10 pm Day: 6 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3855' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an undumped 120 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 11 1985

Maximum pressure 200 psi and shut in 150 psi

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton # 083587 Recovered 2700' 5 1/2" casing (if additional description is necessary, use BACK of this form.)

INVOICED (Do not observe this plugging.)

Signed Robert B. Tarbutton (TECHNICIAN)

DATE 3-12-85

INV. NO. 7299