

To: 1 041231
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

2-20

API NUMBER 15- 185-23,043-0000

SW NE SE, SEC. 17, T 25 S, R 14 W
1650 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5010

Lease Name Toland Well # A-1

Operator: Knighton Oil Company, Inc.

County Stafford 138.12

Name & Address 221 S. Broadway, Ste. 710

Well Total Depth 4250 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: Day: 19 Month: -2 Year: 19 97

Plugging proposal received from Rich Wheeler

(company name) Duke Drilling Co. (phone) 316-267-1331

to fill hole with heavy mud and spot cement through drill pipe Anhydrite 889-911'

1st plug at 911' with 50 sx cement, 2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

1997 FEB 26

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:15 p.m. Day: 20 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 911' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 26 1997

INV. NO. 47669

Signed Stephen J. Pfeifer (TECHNICIAN)

EFFECTIVE DATE: 1-27-97

State of Kansas

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 185-23,043

FORM MUST BE SIGNED

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

ALL BLANKS MUST BE FILLED

Expected Spud Date January 29 1997

Spot East SW NE SE Sec 17 Twp 25 S, Rg 14 XX West

OPERATOR: License # 5010 Name: Knighton Oil Company, Inc. Address: 221 S. Broadway, Suite 710 City/State/Zip: Wichita, Kansas 67202 Contact Person: Earl M. Knighton, Jr. Phone: (316) 264-7918

1650 feet from South/North line of Section 990 feet from East/West line of Section IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 5929 Name: Duke Drilling Company

County: Stafford

Lease Name: Toland Well #: A-1

Field Name: Wildcat

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Lansing

Nearest lease or unit boundary: 990

Ground Surface Elevation: 1978 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 180'

Depth to bottom of usable water: 230'

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 250'

Length of Conductor pipe required: N/A

Projected Total Depth: 4400'

Formation at Total Depth: Arbuckle

Water Source for Drilling Operations: well X farm pond other

Well Drilled For: Well Class: Type Equipment:

X Oil Enh Rec Infield X Mud Rotary X Gas Storage Pool Ext Air Rotary OWWO Disposal X Wildcat Cable Seismic; # of Holes Other

If OWWO: old well information as follows:

Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

Will Cores Be Taken? yes X no If yes, proposed zone:

Exp. 7/22/97

AFFIDAVIT

250' Alt. I Req.

RECEIVED

KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

If it is agreed that the following:

Pusher Rub Wheeler SPUD DATE 2-7-97 INIT. MM LENGTH SURFACE PLANNED 250'

RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLED AHEAD? N SIZE HOLE SURFACE PIPE 2 1/2" @ 267' CONDUCTOR ANHYDRITE T-889 B-911 ELEVATION (4200)

TD 4250 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N

Arbuckle Plug @ If need Ft. W/ 40 SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 911 Ft. W/ 50 SX

1/2 Base Anhy. @ Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 300 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling)

TECHNICIAN SP DATE 2-19-97

TYPE OF CEMENT 10/40 for 26' 911

STARTING TIME (AM/PM) DATE

COMPLETION TIME 12:15 (AM/PM) DATE 2-20

CEMENT COMPANY Allied

RECEIVED KANSAS CORP COM 27 FEB 26 1997