

1 120422

5-2/ 15-185-00309-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 5/11/56

SE SE NE, SEC. 7, T 25 S, R 14 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Moody Well # 1

Operator: Nadel & Gussman

County Stafford 144.01

Name & Address P.O. Box 14

Well Total Depth 4431 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 21 Month: 5 Year: 19 90

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4259' PBD 4402' Perfs at 4166'

1st plug sand back to 4110' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Mike Wilson

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 21 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4110' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 250 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2000' of 5 1/2" casing.

Additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED RECEIVED STATE CORPORATION COMMISSION CONSERVATION DIVISION WICHITA, KANSAS DATE 6-17-90 1990 5-2490 INV. NO. 2832

Signed [Signature] (TECHNICIAN)