

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-099-20620-00-00  
Spot: NENENW Sec/Twnshp/Rge: 21-34S-20E  
4876 feet from S Section Line, 3043 feet from E Section Line  
Lease Name: LINK Well #: 4  
County: LABETTE Total Vertical Depth: 423 feet

Operator License No.: 9386  
Op Name: GUS JONES CABLE TOOL SERVICE, LL  
Address: 149 RD 25  
ELK CITY, KS 67344

Well Type: ST UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 9386 Plug Co. Name: GUS JONES CABLE TOOL SERVICE, LLC  
Proposal Rcvd. from: DONALD (GUS) JONES Company: \_\_\_\_\_ Phone: (620) 332-7637

Proposed Plugging Method: 5 1/2 INCH CASING CEMENTED WITH HIGH TEMPERATURE LUMINITE CEMENT WITH 40 PER CENT SILICA FLOUR. 1 1/2 INCH TUBING WELDED TO OUTSIDE (?) OF CASING FOR THERMOCOUPLE. PERFORATED FROM 351 TO 366 FT. WITH 6 SHOTS PER FOOT. FRACTURED WITH 3000 GALLONS PAD, 3000 GALLONS FRAC FLUID WITH 1 LB./GAL 20/40 MESH SAND, 2000 GALLONS FLUSH.

Plugging Proposal Received By: RUSSELL HINE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/19/2009 1:00 PM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran 3/4" in thermocouple and plugged 4 sacks. Hooked to 5-1/2" and created a rate of flow.  
Pumped 50 sacks of 60/40 pozmix and shut in at 400psi

Perfs: \_\_\_\_\_

KCC WICHITA

NOV 09 2015

RECEIVED

RECEIVED  
KCC DIST # 3

NOV 05 2015

CHANUTE, KS

RH

Remarks: CORRECTED FOOTAGES/GPS 7/15/2015

Plugged through: CSG

District: 03

Signed \_\_\_\_\_

*Russell Hine*

(TECHNICIAN)