

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-24037-00-00  
Spot: SENWNWSE Sec/Twnshp/Rge: 4-14S-11W  
2272 feet from S Section Line, 1985 feet from E Section Line  
Lease Name: CURTISS Well #: #1  
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 33813  
Op Name: JASON OIL COMPANY, LLC  
Address: 3718- 83RD ST PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>SURF</u>	<u>8.625</u>	<u>471</u>		<u>225 sx</u>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2015 12:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: JAY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-4477

Proposed Plugging Method: Ordered 230 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE  
Date/Time Plugging Completed: 09/30/2015 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st plug @3255 w/50 sx  
2nd plug @650 w/50 sx  
3rd plug @401 w/90 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx

Perfs:

KCC WICHITA  
OCT 26 2015  
RECEIVED


Remarks: QUALITY OILWELL CEMENTING

Plugged through: DP

10/28/15 CKM

District: 04

Signed



(TECHNICIAN)

CM

OCT 01 2015