

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21215-00-01
Spot: SESWSWSE Sec/Twnshp/Rge: 35-28S-20W
302 feet from S Section Line, 2032 feet from E Section Line
Lease Name: SHERER B Well #: 1
County: KIOWA Total Vertical Depth: 4724 feet

Operator License No.: 33514
Op Name: JO-ALYN OIL CO., INC.
Address: PO BOX 446
LAVERNE, OK 73848

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5069		WITH 275 SX CMT
SURF	8.625	620		WITH 400 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/20/2015 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE LEIKER Company: LEIKER WELL SERVICE Phone: (620) 793-2336

Proposed Plugging Method: 1ST PLUG AT 4650' WITH 25 SX CMT. 2ND PLUG AT 650' WITH CMT TO SURFACE. PRESSURE BACKSIDE TO 300# WITH CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2015 11:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

PBTD 4909'. 1ST PLUG AT 4694' WITH 25 SX CMT. 2ND PLUG AT 647'.
CIRCULATED CMT TO SURFACE WITH 55 SX CMT. PULLED TBG & TOPPED OFF
WITH 15 SX CMT. BACKSIDE WAS FULL.

KCC WICHITA
OCT 26 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

10/28/15 CKM

District: 01

RECEIVED
OCT 21 2015
KCC DODGE CITY

Signed Eric MacLaren
SA (TECHNICIAN)