

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22073-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 35-11S-31W
380 feet from S Section Line, 1830 feet from W Section Line
Lease Name: LOCKWOOD Well #: 1-35
County: GOVE Total Vertical Depth: 4609 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3608		685 SX
SURF	8.625	342		249 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2015 11:00 AM
Plug Co. License No.: 33302 Plug Co. Name: EVERGREEN WELL SERVICE COMPANY
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 2496' w/225 sx cement.
Perforations at 4190' - 4194', 4216' - 4220' and 4432' - 4434'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2015 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4420' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 3095' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2090' and pumped 75 sx cement. Pulled tubing to 1091' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 10 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.04868 -100.73344

Perfs:


Top	Bot	Thru	Comments
4432	4434		
4216	4220		
4190	4194		

Remarks: GLOBAL CEMENT TICKET # 2515

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

10/28/15 CKM

SEP 30 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 15 2015

CONSERVATION DIVISION
WICHITA, KS