

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22213-00-00
Spot: SENWNESW Sec/Twnshp/Rge: 35-11S-31W
2150 feet from S Section Line, 1950 feet from W Section Line
Lease Name: LOCKWOOD Well #: 2-35
County: GOVE Total Vertical Depth: 4670 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4667		665 SX
SURF	8.625	325		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2015 3:30 PM
Plug Co. License No.: 6490 Plug Co. Name: GREEN COUNTRY WELL SERVICE
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 2503' w/465 sx cement.
Perforations at 4036' - 4038', 4032' - 4034', 4068' - 4070', 4080' - 4082', 4149' - 4153', 4446' - 4448', 4585' - 4587' and 4606' - 4608'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/24/2015 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4516' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 3590' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2621' and pumped 75 sx cement. Pulled tubing to 1626 and pumped 130 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 15 sx cement. Pressured backside to 300 psi.
GPS: 39.05359 -100.73286

Perfs:

Top	Bot	Thru	Comments
4606	4608		
4446	4448		
4080	4082		
4032	4034		

KCC WICHITA
OCT 26 2015
RECEIVED

Remarks: GLOBAL CEMENT TICKET # 2513

Plugged through: TBG

District: 04

Signed *Marvin Mills* (TECHNICIAN) CM 10/28/15 CKM

OCT 01 2015