

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-181-20599-00-00
Spot: NENWSENE Sec/Twnshp/Rge: 9-6S-37W
1582 feet from N Section Line, 787 feet from E Section Line
Lease Name: JOAN DEEDS Well #: 1
County: SHERMAN Total Vertical Depth: 5030 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4630		
PROD	5.5	4954		205 SX
SURF	8.625	303		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2015 12:00 PM
Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 1000 # gel and 600 # hulls.
8 5/8" surface casing set at 303' w/200 sx cement.
5 1/2" production casing set at 4954' w/205 sx cement
TD 5030'. PBTD 4630'
Perforations: 4640' - 4644' shut off. Open perforations: 4625' - 4626', 4536' - 4540'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2015 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 3085' and 2145'. Ran tubing to 4514' and pumped 1000 # gel, followed by 80 sx cement w/250 # hulls. Pulled tubing to 3095' and pumped 150 sx cement w/150 # hulls. Pulled tubing to 1563' and pumped 150 sx cement w/150 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" casing and pumped 25 sx cement. Casing full. Connected to 8 5/8" surface casing and pumped 25 sx cement. Pressured to 300 psi.

GPS: 39.55050 -101.44830

Perfs:

Top	Bot	Thru	Comments
4640	4641		
4625	4626		

Remarks: GLOBAL OILFIELD SERVICES TICKET # 2517

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

OCT 01 2015

OCT 15 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

10/28/15 ckm