

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22187-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 18-22S-11W
1699 feet from S Section Line, 4909 feet from E Section Line
Lease Name: ROSS Well #: 1
County: STAFFORD Total Vertical Depth: 3646 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3641	1805	WITH 150 SX CMT
SURF	8.625	334		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2015 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 3587' WITH 5 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2015 2:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SAND BACK TO 3587' WITH 5 SX CMT. 1ST PLUG PUMPED 25 SX CMT AT 1750' TO CONTROL WELL FLOWBACK. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3641	3646	OH	

KCC WICHITA
OCT 20 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

10/28/15 CKM

District: 01

Signed Larry Harris
(TECHNICIAN)

RECEIVED
OCT 16 2015
KCC DODGE CITY