

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23860-00-00
Spot: NWSEENW Sec/Twnshp/Rge: 20-22S-11W
2075 feet from N Section Line, 2025 feet from W Section Line
Lease Name: AIKEN Well #: 1-20
County: STAFFORD Total Vertical Depth: 3665 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3648	2375	WITH 180 SX CMT
SURF	8.625	343		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2015 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3492' WITH 5 SX CMT. PLUG AT 620' 10 SX GEL & 50 SX CMT. PLUG AT 382' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE
Date/Time Plugging Completed: 10/09/2015 1:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SANDED BACK TO 3492' WITH 5 SX CMT. 1ST PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 382' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3569	3571		
3556	3558		

KCC WICHITA
OCT 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

10/28/15 CKM

District: 01

Signed Larry Harris
(TECHNICIAN)

RECEIVED
OCT 16 2015
KCC DODGE CITY