

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-20645-00-01
Spot: S2NWSWSE Sec/Twnshp/Rge: 12-1S-26W
989 feet from S Section Line, 2310 feet from E Section Line
Lease Name: COZAD Well #: 34-12
County: DECATUR Total Vertical Depth: 3368 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: PO BOX 21598
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3368		150 SX
SURF	8.625	282		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2015 9:00 AM
Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC
Proposal Rcvd. from: ERIC GREEN Company: GREEN OIL FIELD SERVICES, LLC Phone: (785) 635-5132

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/350 # hulls.
Production perforations: 3226' - 3230'.
DV Tool at 1889' w/450 sx cement.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2015 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3213' and pumped 70 sx cement w/250 # hulls. Pulled tubing to 2218' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 1102' and pumped 90 sx cement to circulated cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 20 sx cement. Shut in pressure 300 psi.

GPS: 39.97512N -100.18654W

Perfs:

Top	Bot	Thru	Comments
3226	3230		

KCC WICHITA
OCT 26 2015
RECEIVED

Remarks: GLOBAL CEMENTING

Plugged through: TBG

10/28/15 CM

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

OCT 19 2015