

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Cities Service Company

API NO. 15-151-21,078-0005

ADDRESS 209 E. William  
Wichita, Kansas 67202

COUNTY Pratt

FIELD Wit GRIZZELL

\*\*CONTACT PERSON Richard F. Adams  
PHONE (316) 265-5624

PROD. FORMATION Mississippi

LEASE Grizzell "C"

PURCHASER The Permian Corporation

WELL NO. 1

ADDRESS Box 641  
Hays, Kansas 67601

WELL LOCATION C W/2 NE SW

1980 Ft. from South Line and

1650 Ft. from West Line of

the SEC. 3 TWP. 26S RGE 15W

DRILLING Sterling Drilling Company

CONTRACTOR

ADDRESS Box 129

Sterling, Kansas 67579

PLUGGING

CONTRACTOR

ADDRESS

TOTAL DEPTH 4510' PBD 4460'


SPUD DATE 1-25-82 DATE COMPLETED 3-7-82

ELEV: GR 2034' DF 2039' KB 2043'

DRILLED WITH (CABLE) (ROTARY) (XXX) TOOLS

Amount of surface pipe set and cemented 8 5/8" - 409' DV Tool Used? No

WELL PLAT



KCC  
KGS  
(Office Use)

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS, I,

W. J. Devaney OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS W. J. Devaney (XXX)(OF) Cities Service Company


OPERATOR OF THE Grizzell "C" LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 7 DAY OF March, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.



(S) W. J. Devaney

Signature of Jacqueline Pierce, Notary Public

MY COMMISSION EXPIRES: 2-27-85

\*\*The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0'	240'		
Shale	240'	415'		
Shale and Lime	415'	1000'		
Anhydrite	1000'	1015'		
Shale	1015'	1810'		
Lime and Shale	1810'	3860'		
Lime	3860'	4425'		
Lime and Shale	4425'	4510'		
RTD	4510'			

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	409'	Class "A"	300	3% CaCl <sub>2</sub>
Production	7 7/8"	5 1/2"	14#	4509'	50-50 Pozmix	175	10% NaCl + .75% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1		4398'-4399'

TUBING RECORD

Size	Setting depth	Packer set at
2" EUE	4403'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Treat with 250 gallons MCA	4398'-4399'

Date of first production March 7, 1982	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil 60 bbls. Gas --- MCF Water 48% 55 bbls. Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)		Perforations 4398'-4399'



CITIES SERVICE COMPANY  
ENERGY RESOURCES GROUP

209 East William  
800 Sutton Place Building  
Wichita, Kansas 67202  
(316) 265-5624

March 26, 1982

State Corporation Commission  
of Kansas  
200 Colorado Derby Building  
200 West First Street  
Wichita, Kansas 67202

Attn: Mr. Tom Leiker

RE: Grizzell "C" #1  
Sec. 3-26S-15W  
Pratt County, Kansas

Dear Mr. Leiker:

Please change the Field Name to the Grizzell on the Affidavit of Completion Form (ACO-1), which was submitted to your office on March 11, 1982.

Very truly yours,

*Richard E. Adams*

Richard E. Adams  
Supervisor Oil and Gas Systems  
Mid-Continent North Region

REA/ct

cc: Mr. Donald E. Hewitt

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1982 3-29-82

CONSERVATION DIVISION  
Wichita, Kansas