

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED FORM CP-1
Rev. 03/92
KANSAS CORPORATION COMMISSION

JAN 23 1995

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-20,818-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)

ADDRESS 6427 E Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE CUDNEY A WELL# 4 SEC. 4 T. 26 R. 16W (East/West)
Irregular Section SPOT LOCATION/QQQQ COUNTY Edwards

440' FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

440' FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL DEA SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 441' CEMENTED WITH 400 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4532' CEMENTED WITH 275 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4076 to 4080 Lansing

ELEVATION 2084KB T.D. 4540 PSTD NA ANHYDRITE DEPTH 1085 (+999)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and Halliburton Plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick PHONE# (316) 995-3171

ADDRESS P.O. Box 158 City/State Belpre, Ks. 67519

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893

ADDRESS P.O. Box 847 Pratt, Ks. 67124 PHONE # (316) 672-2531
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not Known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/20/95 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 25, 1995

F G Holl Company L L C
6427 E Kellogg P O Box 780167
Wichita KS 67278-0167

Cudney A 4
API 15-047-20,818 -0300
440 FNL 440 FWL
Sec. 04-26S-16W
Edwards County

Dear Art Merrick,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760

JAN 23 1985

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

CONSERVATION DIVISION
WICHITA, KS

15-047-20618-0000

WELL LOG - - - - - CUDNEY "A" 4-4
Located: 420' FNL; 2300' FEL, NE/4, Section 4-26S-16W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: Febauray 27, 1981
COMPLETED: March 7, 1981

TOTAL DEPTH: 4540'

LOG

CASING RECORD

0 - 375 Sand
375 - 445 Shale and Red Bed
445 - 1084 Shale
1084 - 1100 Anhydrite
1100 - 4490 Lime and Shale
4490 - 4540 Lime

Ran 11 joints 8 5/8", 28# OD casing.
430' set at 441' K.B. Cemented with
400 sacks 60/40 Pozmix with 3% cc.
Plug down at 7:00 PM, 2-28-81, by Howco.

Ran 143 joints 4 1/2", 10.5# OD casing.
4523' set at 4532' K.B. Cemented with
100 sacks Howco Lite, followed with
175 saks 50/50 Pozmix with 18% salt,
5# gilsonite per sack, 3/4 of 1% CFR-2,
1/8# flocele per sack and 1/8# tuffiber
per sack. Plug down at 9:30 PM, 3-7-81,
by Howco.

Deviation Surveys: 1 3/4° at 2153'
1 1/2° at 4105'