

RECEIVED
 STATE OF KANSAS CORPORATION COMMISSION
 CONSERVATION DIVISION
 200 Colorado Derby Building
 Wichita, Kansas 67202

FORM CP-1
 Rev. 03/92

JAN 23 1995

WELL PLUGGING APPLICATION FORM
 (PLEASE TYPE FORM and File ONE COPY)
 CONSERVATION DIVISION
 WICHITA, KS

API # 15-047-20,865-400 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company L.L.C. KCC LICENSE # 5056
 (owner/company name) (operator's)

ADDRESS 6427 E Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE CUDNEY A WELL# 7 SEC. 4 T. 26 R. 16W (East/West)

Irregular Section SPOT LOCATION/QQQQ COUNTY Edwards

330' FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

330' ^{LOT 4} FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL DGA SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 449' CEMENTED WITH 400 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4562' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4086 to 4087 Lansing

ELEVATION 2096KB T.D. 4590' PBDT 4403' ANHYDRITE DEPTH NA
 (G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and Halliburton Plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick PHONE# (316) 995-3171

ADDRESS P.O. Box 158 City/State Belpre, Ks. 67519

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893
 (company name) (contractor's)

ADDRESS P.O. Box 847 Pratt, Ks. 67124 PHONE # (316) 672-2531

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not Known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/20/95 AUTHORIZED OPERATOR/AGENT: [Signature]
 (signature)



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 25, 1995

F G Holl Company L L C
6427 E Kellogg P O Box 780167
Wichita KS 67278-0167

Cudney A 7
API 15-047-20,865
330 FNL 330 FEL
Sec. 04-26S-16W
Edwards County

Dear Art Merrick,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - CUDNEY "A" 7-4
Located: 330' FNL; 330' FEL, Lot 4, Section 4-26S-16W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

RECEIVED
KANSAS CORPORATION COMMISSION

COMMENCED: May 23, 1981
COMPLETED: May 31, 1981

JAN 23 1995

TOTAL DEPTH: 4596'

CONSERVATION DIVISION
WICHITA, KS

<u>LOG</u>	<u>CASING RECORD</u>
0 - 453 Sand and Clay	Ran 11 joints 8 5/8", 20# casing. 438.09' pipe set at 449' K.B. Cemented with 400 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 4:00 AM, 5-24-81, by Howco.
453 - 1065 Shale	
1065 - 1083 Anhydrite	
1083 - 1700 Shale	
1700 - 4596 Lime and Shale	Ran 106 joints 4 1/2", 10.5# OD casing. 4585.18' pipe set at 4594' K.B. Cemented with 100 sacks Howco Lite, tailed in with 175 sacks 50/50 Pozmix with 2% gel, 18% salt, 5# gilsonite, 3/4 of 1% CFR-2, 1/8# flocele and 1/8# nylon fiber per sack. 20 bbls. mud flush ahead of cement. Plug down at 1:00 PM, 5-31-81, by Howco.

Deviation Surveys: 1° at 1908'
3/4° at 4590'