

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 15-047-10008-0000 (of this well)
None (too old)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Robert F. White OPERATORS LICENSE NO. 5061 ^{6/90}

ADDRESS 2400 N. Woodlawn, #114, Wichita, KS 67220 PHONE # (316) 688-1616

LEASE (FARM) Belcher Unit WELL NO. 1 WELL LOCATION C NW NE COUNTY Edwards

SEC. 19 TWP. 26S RGE. 18 ~~XXXX~~(W) TOTAL DEPTH 4723' PLUG BACK TO 3400'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 209' CEMENTED WITH 200 SACKS

CASING SIZE 5 1/2" SET AT 4723' CEMENTED WITH 300 SACKS

PERFORATED AT 4689' - 4700' (water recovered) Bridge plug set at 3400'. Perf

Tarkio at 3336' - 3341' - completed there.

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Dump 100' sand to cover perms at 3336' - 3341'

Dump 10 sax cement on top of sand. Pull casing. Mud hole to 300'. Set bridge

and fill hole to surface with cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? attached IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 25, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Robert F. White

PHONE # (316) 688-1616

RECEIVED
STATE CORPORATION COMMISSION
688-1616

ADDRESS 2400 N. Woodlawn, #114, Wichita, Kansas 67220

PLUGGING CONTRACTOR Great Bend Casing Pulling Inc.

LICENSE NO. 4635

NOV 17 1989

CONSERVATION DIVISION
Wichita, Kansas

ADDRESS P.O. Box 768, Great Bend, KS 67530

PHONE # (316) 793-9711

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: _____

(Operator or Agent)
Robert F. White

DATE: November 16, 1989

①



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
FEB 20 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

November 20, 1989
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

15-047-10008-0050

Robert F. White
2400 N. Woodlawn, #114
Wichita, KS 67220

Belcher Unit 1
C NW NE
Sec. 19-26-18W
Edwards County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760

15-047-10008-0000


ORIGINAL OPERATOR

Operator <i>Robert F. White</i> <i>Aylward DRIG CO.</i>		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDOW, ETC.:
Well No. 1	Lease Name <i>BELCHER</i>	<i>GAS. LIQ. L.</i>
S. 18 T. 26 S. R. 16 E. W.		
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		

Company- AYLWARD DRIG. CO., KENNETH RUPP ET AL SEC. 19 T. 26 R. 18W
 Farm- Belcher No. 1 C SW NE

Total Depth. 4726'
 Comm. 8-22-63 Comp. 9-9-63
 Shot or Treated.
 Contractor. Aylward Drilling Co.
 Issued. 4-11-64

County Edwards
 KANSAS



CASING:
 8 5/8" 209' cem w/200 sx.
 5 1/2" 4723' cem w/300 sx.

Elevation. 2197' DE

Production. 590 MCFG

Figures indicate Bottom of Formations.

sand	100
shale & shale	700
shale	2320
shale & lime	2475
lime & shale	3090
lime	3155
lime & shale	3331
lime	3346
sand	3375
lime & shale	4190
lime	4726 RTD
Total Depth	

TOPS: LOG

Chase Group	2465
Council Grove Group	2640
Wabaunsee Group	3259
Pillsbury (Langdon) Shale	3315
Tarkio Sandstone	3336
Topeka	3554
Heebner	3988
Lansing-Kansas City	4126
Base Kansas City	4509
Marmaton	4532
Mississippi	4666

RECEIVED
 STATE CORPORATION COMMISSION

NOV 17 1989

CONSERVATION DIVISION
 Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Robert F. White</i>
	Signature
	<i>Operator</i>
	Title
	<i>Dec 19 1978</i>
	Date