

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 4 1965

2-4-65

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company 15-047-30000-0003

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Belcher "A" Well No. # 1

Location C SE NW Sec. 17 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 3422'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Western Petroleum Co., Inc.

Address: 925 Patton, Great Bend, Kansas License No. _____

Operation Completed: Hour 1:00AM Day 3rd Month Feb. Year 1965

The Above well was plugged as follows:

315' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid
level in the hole was at 170'. 1st cementing plug and 1/4 sack of hulls
was pushed in fluid to 280', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

INVOLCED

I hereby certify that the above well was plugged as herein stated.

DATE 2/4/65

Signed: Archie Elving
Well Plugging Supervisor

INV. NO. 638-W