

KANSAS

*2*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

7-17-72  
RECEIVED  
STATE CORPORATION COMMISSION  
JUL 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Glen Rupe 15-047-20082-0000  
Complete Address 925 O.W. Garvey Bldg. Wichita, Ks  
Lease Name Odgen Well No. 1  
Location NW/SW/NE Sec. 20 Twp. 26 Rge. 18 (E) (W) W  
County Edwards Total Depth 4854  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Russ Casing Pulling Co. Inc.  
Address Box 1182 Great Bend, Ks License No. 623  
Operation Completed: Hour 9:00 AM Day 13 Month 7 Year 1972

The above well was plugged as follows:

315 ft 8 5/8 surface pipe cemented with 250 sacks. 4851 ft 4 1/2 long  
string cemented with 175 sacks. Top perf. 4692 ft. Sand to 4600 ft,  
4 sacks cement with bailer. Pulled 2500 ft 4 1/2. Set 10 ft rock  
bridge at 225 ft. Fill hole with 3 1/2 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 7/17/72  
INV. NO. 6034-U