

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED

STATE CORPORATION COMMISSION

DEC - 8 1981

12-8-81

API Number 15-047-20,829 109,000 ✓

CONSERVATION DIVISION  
Wichita, Kansas

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Edwards Oil Inc.

Complete Address 1215 E 30th Bay 306 Hutchinson Kansas 67501

Lease Name Russell Well No. 1

Location C-5 1/2 18E SW Sec. 21 Twp. 25S Rge. 16W (East)(West)

County Edwards Total Depth 4423'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A     

Other well as hereinafter indicated Well was completed but never produced

Plugging Contractor Kelco Casing pulling

Address Box 176 Chase Kansas 67524 License No. 683

Operation Completed: Hour: 3:40 PM Day: 2 Month: December Year: 1981

Plugging Operations attended by Agent?: All ✓ Part      None     

The above well was plugged as follows:

There is 472' of 8 5/8" surface casing cement circulated with 400 lbs cement. The cement was common with 4% gel 3% C.C. There is 4418 1/2" production pipe cemented with 175 lbs cement 50/50 pause 18% salt 3 1/2% 1st plug after spacing bottom hole sand to 4 3/4' 4 lbs cement. 2nd plug pumped in 4 lbs hulls, 25 lbs gel 150 lbs cement. The cement used was 50/50 pause 4% gel 3% C.C. There was 2600' of production pipe recovered. Mr. Keith Smith of Edwards oil had Kelco's pull off hole October 1, 1981. I called Mr. Smith October 2, 1981 to find out when he was going to finish the plugging.

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: Paul Smith  
Conservation Division Agent

DATE 1-19-82

ENV. NO. 8909-W

(over)

I called him again on 11-17-81 & 11-30-81 to get it plugged  
He always put me off for a few days, Halliburton Co out of  
Great Bend Kansas finally completed the plugging in  
December. Mr. Wurub told me there was no gas pressure  
shut in the day they went to the location  
shut in pressure after penning down plug was 100 lbs.

Paul Lutke

143,75