

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas

11-30-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leben Drlg. Co. Inc.

Complete Address Box 485 Great Bend, Ks

Lease Name Wilson Well No. 1

Location NE/NE/SW Sec. 26 Twp. 25 Rge. 16 (E) (W)

County Edwards Total Depth 4460

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Co. Inc.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 11:30 AM Day 25 Month 11 Year 1970

The above well was plugged as follows:

394 ft of 8 5/8 surface pipe circulated. 4460 ft of 5 1/2 long string
cemented with 150 sacks. Top perf. 4354 ft. Sand back to 4300 ft,
5 sacks cement with bailer. Pulled 3218 ft of 5 1/2. Pumped 3 sacks
hulls, 15 sacks gel. & 100 sacks cement to base of cellar.

Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/1/70

INV. NO. 2921-U

Signed: M. Russell Biberstein
Well Plugging Supervisor