

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

SEP 24 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name Mellon Well No. # 1

Location App. C SW NE Sec. 25 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4459'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:15PM Day 23rd Month Sept. Year 1965

The Above well was plugged as follows:

373' of 8 5/8" surface pipe, cemented with 250 sacks. 4458' of 5 1/2" long string, cemented with 200 sacks. Plug back to 4421'. Top perferation 4317'. Bottom of the hole was sanded to 4300', and cemented with 5 sacks. 2372' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 300', rock bridge from 300' to 290'. 10 sacks of cement was mixed in a barrel, and put on plug at 290', through the dump bailer and let set over-night. Next morning hole was bailed dry, and 15 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Achie Elving
Well Plugging Supervisor

INVOICED

DATE 9/27/65
INV. NO. 1861-W