

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20,870-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name C. L. Morris Oil Corp

Complete Address P.O. Box 204, 200 Hardage Center, 100 South Main, Wichita, Kansas

Lease Name Grizzell Shepard Well No. 1

Location 140' NW of C.S.E Sec. 23 Twp. 25S Rge. 16W (East)(West)

County Edwards Total Depth 4450

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rams Drilling

Address 1005 Main, 200 Hardage Center, Wichita, Kas.

Operation Completed: Hour: 8:30 PM Day: 24 Month: Dec Year: 1981

Plugging Operations attended by Agent?: All Part None

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1981
CONSERVATION DIVISION
Wichita, Kansas

12-1-81

The above well was plugged as follows:

There is 370' of 8 5/8" surface casing cement circulated. There is 4450' of 4 1/2" production pipe cemented to 3800'. There is a plug at 4357'. The perforations are from 4351' to 4354'. 1st plug sandbed off bottom to 4260' with 4 Sbk. of cement. 2nd plug 5 Sbk. Jell then 5 Sbk. bulbs & 5 Sbk. Jell then 50 Sbk. of cement released. ~~There is a~~ rubber plug & put 50 Sbk. on top of it. Plugging accomplished by Halliburton Co. Great Kans.

There were _____ of production pipe recovered.

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED
DATE 12-14-81
INV. NO. 8711-W

Signed: Paul Luthi
Conservation Division Agent

W E L L L O G

WELL NAME: Grizzell - Shepard OPERATOR: The C. L. Morris Oil Corp.
SPUD DATE: May 23, 1981 CONTRACTOR: Ramco Drilling
COMPLETION DATE: June 12, 1981 CASING:

LOCATION: 140' NW of C SE¼
 23-25S-16W
 Edwards County, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand & Shale	0	370
Sand & Shale	370	1010
Sand & Shale	1010	1469
Sand & Shale	1469	1732
Sand & Shale	1732	2100
Sand & Shale	2100	2365
Sand & Shale	2365	2595
Lime & Shale	2595	2792
Lime & Shale	2792	3051
Shale & Lime	3051	3251
Lime & Shale	3251	3376
Lime & Shale	3376	3530
Shale & Lime	3530	3702
Shale & Lime	3702	3866
Shale & Lime	3866	3955
Shale & Lime	3955	4048
Shale & Lime	4048	4148
?	4148	4233
Shale & Lime	4233	4320
Shale & Lime	4320	4330
	4330	4358
Cherokee	4357	
	4357	4375
	4375	4430
	4430	4450
RTD	4450	

STATE OF KANSAS)
)
COUNTY OF SEDGWICK)


I certify that the above information is true and correct to the best of my knowledge.

THE RAMCO DRILLING CORPORATION

By: *J. W. Grizzell*

Subscribed and sworn to before me on this 17th day of August, 1981.

Sandra Kay May
Notary Public
Sandra Kay May



6-5-84