

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name D.R. Lauck Oil Co Inc

Complete Address 301 S Broadway Wichita, KS

Lease Name Ansel Well No. 1

Location SE/SE/NE Sec. 23 Twp. 25^B Rge. 16 (E) (W) W

County Edwards Total Depth 4733

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers Inc

Address Box 486 Ellinwood, KS License No. 462

Operation Completed: Hour 10:00 AM Day 15 Month 6 Year 1974

The above well was plugged as follows:

335 ft 8 5/8 surface cemented with 250 sacks. 4733 ft 5 1/2 long string
cemented with 125 sacks. Top perf. 4298 ft. Sand to 4200 ft, 5
sacks cement with bailer. Pulled 2273 ft 5 1/2. Pump 2 sacks hulls,
10 gel, 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/18/74

INV. NO. 9311-W

Signed: Russell B. Hunter
Well Plugging Supervisor