


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ford County, Sec. 33 Twp. 25 Rge. 21 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE NW

Lease Owner H & H Supply Company

Lease Name Troy Mahoney Butler Well No. 5

Office Address P. O. Box 95226

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 4-8 19 69

Application for plugging approved 4-9 19 69

Plugging commenced 4-21 19 69

Plugging completed 4-28 19 69

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves

Producing formation Depth to top Bottom Total Depth of Well 4835 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	192	None
				4 1/2	None	1111

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Rigged up. Pumped 20 sacks of cement to 4000'.

Cleaned out cellar. Rigged up jacks. Shot pipe at 3600'. Working pipe.

Pumped water - 6 loads. Working pipe.

Shot pipe at 3020' - 2510' - 2020' - 1530' and 1116'. Working pipe.  
Pulling pipe.

Pumped 30 sacks of cement. Mudded to 20'. Dumped 10 sacks of cement for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
Address P. O. Box 221 Great Bend, Kansas 67530

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 2 day of May, 19 69

My commission expires May 27, 1969

Notary Public.

COPY

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK WICHITA, KANSAS

COMPANY AMARILLO NATURAL GAS

SEC. 33 T. 25 N. 21W  
LOG. C NE NW

FARM Butler NR 5

COUNTY Ford

TOTAL DEPTH 4835'


DDMM 7-11-66

COMP. 1-19-67

SHOT OR TREATED

CONTRACTOR Mahoney Drlg.

ISSUED 7-6-68



CASING

20	10
15	8 5/8" 192' cem w/ 175 sx
12	6
13	5
	4 1/2" 4327' cem w/ 125 sx

ELEVATION 2353' KI

PRODUCTION DRY/MISS

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE

TOPS: LOG

Lansing	4178
Lansing A Zone	4190
Lansing "B" Zone	4221
Lansing Kansas City	4587
Marmaton	4605
Cherokee	4725
Mississippie	4812
RTD	4835

RECEIVED  
STATE CORPORATION COMMISSION  
APR 9 1969  
CONSERVATION DIVISION  
Wichita, Kansas