


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ford County. Sec. 7 Twp. 25S Rge. (X) 23(W)
Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Graves Drilling Co., Inc.
Lease Name Hart Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 5, 1966
Application for plugging filed October 5, 1966
Application for plugging approved October 5, 1966
Plugging commenced October 5, 1966
Plugging completed October 5, 1966
Reason for abandonment of well or producing formation



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves, Box "F", Sublette, Kansas
Producing formation Depth to top Bottom Total Depth of Well 1580 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 714 feet. Followed by wooden plug and 1/4 sack hulls. Placed 15 sacks cement onto hulls. Mudded up with heavy mud to 353 feet followed by wooden plug and 15 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
11-8-66
NOV 8 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1966

My commission expires April 30, 1967
Betty Brandt Notary Public

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: October 3, 1966
412 Union Center
Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: October 5, 1966
412 Union Center
Wichita, Kansas

CASING RECORD: None set. LOCATION: Hart No. 1
SW SW SW
Section 7-25S-23W
Ford County, Kansas

0 - 43	Sod & clay
43 - 256	Shale, sand & clay
256 - 950	Sand & shale
950 - 1354	Shale & red bed
1354 - 1522	Red bed & shale
1522 - 1560	Anhydrite
1560 - 1580	Shale
1580	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1966
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Phil Graves
President

STATE OF KANSAS)
) SS:
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 28th of October, 1966.

Betty Brandt
Betty Brandt Notary Public

My commission expires:
April 30, 1967