

RECEIVED  
JAN 18 2002

1-18-2002  
TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

CONSERVATION DIVISION  
Wichita, Kansas

LEASE OPERATOR Exxon Mobil Corporation

ADDRESS P.O. Box 4358 Houston, TX 77210

PHONE (713) 431-1828 OPERATORS LICENSE NO. 5208

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-18-01 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 2570 Bottom \_\_\_\_\_ T.D. = 5150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8</u>	<u>1935</u>	<u>-</u>
				<u>5 1/2</u>	<u>3069</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each so  
Mixed 4 sx hulls & 25 sx cmt. to plug perf's from 2570 to 2370. Recovered 1800 ft 5 1/2. Circ. hole w/mud & mixed 50 sx plug from 1800 to 1650, 40 sx from 1050 to 930, 25 sx 550 to 475, 10 sx 40 to 0. Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXXON MOBIL

STATE OF KANSAS COUNTY OF STEVENS, ss.

RICHARD B. LEWIS (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) R.B. Lewis

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 9th day of JANUARY, 2002

Dolores M. Fleming  
Notary Public

My Commission Expires: 8-11-2002

OK