


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Finney County, Sec. 18 Twp. 25S Rge. 34 (W)

Location as "NE/CNW/SW" or footage from lines C NW SE

Lease Owner Petroleum, Inc.

Lease Name FEDERAL "C" Well No. 2

Office Address 800 RH Garvey Building, Wichita, Ks 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 18 19 75

Application for plugging filed (verbal) February 18 19 75

Application for plugging approved (verbal) February 18 19 75

Plugging commenced February 18 19 75

Plugging completed February 18 19 75

Reason for abandonment of well or producing formation No commercial quantities
of gas or oil encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation Depth to top Bottom Total Depth of Well 5120 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	832'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

- 1st Plug Set @2000' with 35 sacks cement.
- 2nd Plug Set @ 950' with 60 sacks cement
- 3rd Plug Set @ 500' with 35 sacks cement.
- 4th Plug Set @ 45' with 15 sacks cement
- Plugged rat hole with 5 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
2-27-75
FEB 27 1975
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Ks. 67202
(Address)

Subscribed and sworn to before me this 26th day of February, 19 75



Nancy E. Haner
Notary Public.

April 8, 1978

CONTRACTOR'S WELL LOG

OPERATOR:	Petroleum, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	FEDERAL "C" #2
LOCATION:	C NW SE Section 18-25S-34W Finney County, Kansas
GEOLOGIST:	Bob Posey
SPUD DATE:	February 4, 1975
COMPLETION DATE:	February 18, 1975

0	41	Sand
41	879	Sand & Shale
879	1280	Sand
1280	1533	Shale & Sand
1533	1765	Sand & Shale
1765	2318	Sand
2318	2630	Shale
2630	3385	Shale & Lime
3385	4000	Lime & Shale
4000	4155	Lime
4155	4300	Lime & Shale
4300	5120	Lime
	5120	Rotary Total Depth

Drilled 832' of 12 1/4" surface hole. Set 8-5/8" casing @ 832'. Cemented with 350 Sacks Halliburton Light Cement, 2% calcium chloride and 150 Sacks Common, 3% calcium chloride. Cement did not circulate. Recemented twice. Gravel packed hole to surface.

Plugged and Abandoned: Set 1st Plug @ 2000' with 35 sacks cement, 2nd Plug @ 950' with 60 sacks, 3rd Plug @ 500' with 35 sacks, 4th Plug @ 45' with 15 sacks. Plugged rat hole with 5 sacks cement. Plugged down @ 5:30 p.m., February 18, 1975. State Plugger: Clarence Thomas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Federal "C" #2, C NW SE Section 18-25S-34W, Finney County, Kansas.


ABERCROMBIE DRILLING, INC.

By: *Jerry A. Langrehr*
Jerry A. Langrehr
Executive Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 26th day of February, 1975.

Nancy E. Haner
Nancy E. Haner, Notary Public

My Commission Expires: 4-8-78



RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1975

CONSERVATION DIVISION
Wichita, Kansas