

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

RECEIVED 15-151-20925-0000  
925  
MAR 24 1986  
API NUMBER 15,151 20,951  
LEASE NAME Kerr

TYPE OR PRINT WICHITA OFFICE  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1  
SPOT LOCATION NE SE NE  
SEC. 23 TWP. 29 RGE. 14 (E) or (W)  
COUNTY Pratt  
Date Well Completed 7-31-81  
Plugging Commenced 3-14-86  
Plugging Completed 3-21-1986

LEASE OPERATOR The Reach Group  
ADDRESS 229 E. Williams, Suite 600, Wichita, Ks.  
67202  
PHONE # (316) 262-1515 OPERATORS LICENSE NO. 8572

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached?

Producing formation Swope Depth to top 4291' bottom 4330 T.D. 4563'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	451'	0'
Production				4 1/2"	4060'	2537'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 2 sks. hulls & 20 sks. cement to 3720' & pressured to 700 lbs.  
Pumped 5 sks. gel & 50 sks. cement 850' to 700'  
Pumped 40 sks. cement 475' to 350'  
Put bridge & 10 sks. cement 40' to 0' Cut off 8 5/8", 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks. 67877

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1986

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-88

