

15-063-20187-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas

Lease Name Beougher Well No. 1

Location C SW NE Sec. 26 Twp. 13 Rge. (E) (W) 30

County Gove Total Depth 4566'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 10 P Day 16 Month 6 Year 1973

The above well was plugged as follows:

RTD 4566' 8 5/8 csg set at 170' cwc. Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 1250' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messerly
Well Plugging Supervisor

DATE 6/19/73

INV. NO. 9527-4