

11-26-87

1 061035

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 069-20,219-0000

C SW SE, SEC. 14, T 29 S, R 27 W/E
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6044

Lease Name Nelson Well # 1

Operator: Stelbar Oil Corporation, Inc.
Name &

County Gray 172.25

Address 155 North Market, Suite 500

Well Total Depth 5300 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1568

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson Oil Company License Number 5146

Address 435 Page Court, 220 West Douglas, Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 26 Month: 11 Year: 19 87

Plugging proposal received from Larry Hendeliter

(company name) Rains & Williamson Oil Company (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2608' GL
Anhydrite 1598'

1st plug at 1598' with 50 sx cement,

2nd plug at 850' with 35 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 a.m. Day: 26 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1598' with 50 sx cement,

2nd plug at 850' with 35 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1987
12-2-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
(did not) observe this plugging.

DATE 12-4-87

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 19142

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 11/5/87 month day year

API Number 15-069-20,219-0000

OPERATOR: License # 6044
Name Stelbar Oil Corporation, Inc.
Address 155 North Market, Suite 50C
City/State/Zip Wichita, KS 67202
Contact Person John C. Shawyer
Phone (316) 264-8378

C. SW 1/4 SE 1/4 Sec. 14 Twp. 29 S. Rg. 27 XX West
660' Ft. from South Line of Section
1980' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5146
Name Rains & Williamson Oil Co.
City/State Wichita, Kansas

Nearest lease or unit boundary line 660' feet
County Gray
Lease Name Nelson Well #1
Ground surface elevation Unknown feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 250'
Depth to bottom of usable water 800' - 850'

IF OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 1580'
Conductor pipe required
Projected Total Depth 5400 feet
Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications.
Date 9/25/87 Signature of Operator or Agent John C. Shawyer Title Vice-President

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 870 feet per Alt. 1 X

This Authorization Expires 4-2-88 Approved By R.H. 10-2-87

Spud 11-12-87

10-7-87 going to set 16' in hole - 1580' +/- using existing w.c.
setting casing - 80'-90'-22" using existing w.c.

C. SW 1/4 SE 1/4 Sec. 14 Twp. 29 S. Rg. 27 XXX West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1580 feet depth with 50 sxs of cement
2nd plug @ 40 feet depth with 10 sxs of cement
3rd plug @ feet depth with sxs of
4th plug @ feet depth with sxs of
5th plug @ feet depth with sxs of
(a) Rathole with 10 sxs (b) Mousehole with sxs

PUSHER Larry Handletter
TD 5300 FORMATION Muds
SURFACE PIPE 8 3/4 @ 15868
ANHYDRITE 1598 ELEVATION 2608 ft.
STARTING TIME & DATE 11:30 AM 11-26-87
COMPLETION TIME & DATE 5:00 AM 11-26-87
1st PLUG @ 1698 FT. W/ 670 SX
2nd PLUG @ 850 FT. W/ 35 SX
3rd PLUG @ 40-0FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ No SX
CEMENT COMPANY Allied 60/40 w/ 6% yellow
TECHNICIAN Paul Letter No one saw

RECEIVED STATE CORPORATION COMMISSION

DEC 2 1987

CONSERVATION DIVISION Wichita, Kansas