

Tax I 090866
STATE CORPORATION COMMISSION 10-16
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 057-20,550-0000
100' E of
S/2 S/2 NW, SEC. 29, T 29 S, R 22 W/8
2310 feet from NXX section line
1420 feet from W X section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name
Address P.O. Box 783188
Wichita, KS 67278-3188

Lease Name D. Ellis Well # 1
County Ford 174.27
Well Total Depth 5362 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 641

Abandoned Oil Well Gas Well Input Well SWD Well O&A X
Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Co., Inc. License Number 5123
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 15 Month: 10 Year: 1997

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Co., Inc. (phone) 316-262-8427

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1500'
1st plug at 1500' with 50 sx cement,
2nd plug at 670' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1 a.m. Day: 16 Month: 10 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,
2nd plug at 670' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 27 1997

INV. NO. 49342

Signed [Signature] (TECHNICIAN)

State of Kansas -15- NOTICE OF INTENTION TO DRILL 057-20,550-0000 ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 9-21-97

DISTRICT # SEAT Yes X No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 28 97 month day year

Spot 100' East S/2-S/2 NW. Sec. 29. Twp. 29. S. Rg. 22. X West

OPERATOR: License # 4767 Name: Ritchie Exploration, Inc. Address: P.O. Box 783188 City/State/Zip: Wichita, Kansas 67278-3188 Contact Person: Julie Stout Phone: (316) 691-9500

2310 feet from South (North) line of Section 1420 feet from East (West) line of Section IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side) County: Ford Lease Name: D. Ellis Well #: 1 Field Name: unknown Is this a Prorated/Spaced Field? yes X no Target Formation(s): Morrow-Mississippian Nearest Lease or unit boundary: 330 Ground Surface Elevation: 2458.1 est. Feet MSL Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no Depth to bottom of fresh water: 380 Depth to bottom of usable water: 380 Surface Pipe by Alternate: X 1 Length of Surface Pipe Planned to be set: 600 Length of Conductor pipe required: none Projected Total Depth: 5450 Formation at Total Depth: Mississippian Water Source for Drilling Operations: well farm pond X other

CONTRACTOR: License #: 5123 Name: Pickrell Drilling Co., Inc.

Well Drilled For: Well Class: Type Equipment: X All ... Enh Rec ... Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... GWHO ... Disposal X Wildcat ... Cable ... Seismic: ... # of Holes ... Other If GWHO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location: Exp: 3/16/98 AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

Pusher Doyle SPUD DATE 10-4-97 INIT Mlan LENGTH SURFACE PLANNED 620 +/- RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 2 1/2 @ 6 1/2 CONDUCTOR ANHYDRITE T- B- 500 ELEVATION TD 5362 FORMATION Mississippian RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Bug./Council @ Ft. W/ SX Anhydrite Base @ 1500 Ft. W/ 50 SX 1/2 Base Anyh. @ Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 670 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SPM DATE 10-13-97 TYPE OF CEMENT 60/40 620 STARTING TIME 9:00 (AM/PM) DATE 10-15-97 COMPLETION TIME 1:00 (AM/PM) DATE 10-16-97 CEMENT COMPANY Allied