

1 080497

15-151-20925-0000 925-05-50
151-20,951

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NE SE NE , SEC. 23 , T 29 S, R 14

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Kerr Well # 1

Operator: The Reach Group

County Pratt 148.30

Name & Address 229 E. William, Suite 600

Well Total Depth 4563 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 11:00 am Day: 21 Month: March Year: 19 86

Plugging proposal received from Ed Eves

(company name) Midwest (phone) 316-675-8349

were: 4 1/2" at 4060' Perfs at 4308-4313' Pump through 4 1/2" with mud between plugs

1st plug pump 2 sx hulls and 20 sx cement to bottom pushing plug to 4250'

2nd plug at 850' with 50 sx cement

3rd plug at 480' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 pm Day: 21 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to bottom and pushed plug to 4250'. 2nd plug at 850' with 50 sx cement, 3rd plug at 480' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 2537' 4 1/2" casing. Used common cement by Midwest.
(If additional description is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION

DATE APR 1 1986

MAR 31 1986

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 13220 3-2/

CONSERVATION DIVISION
Wichita, Kansas

3-31-86