

3-22-88 15-151-21450-00-00

1 040073

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-23,355  
NE SE SW, SEC. 22, T 29 S, R 14 W/E  
990 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Kerr Well # B-1

Operator: Texas Energies, Inc.

County Pratt 158.60

Name & Address P.O. Box 947

Well Total Depth 4880 feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 176, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 22 Month: 3 Year: 19 88

Plugging proposal received from Ted Moff

(company name) Texas Energies, Inc. (phone) 316-672-7838

were: 4 1/2" at 4723' CTBP at 4700' Perfs at 4590-4596' DV tool at 2439' Elevation 1989'  
1st plug sand back to 4675' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 a.m. Day: 22 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to about 3500' and dumped 4 sx cement on top  
of sand through bailer. When the tubing was pulled, a Halliburton EZ-E drill tool was backed  
off and left in the hole around 3500'. Tool is closed.

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
100 lbs. hulls, and 100 sx cement.

Maximum pressure 550 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2000' of 4 1/2" casing  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
3-29-88  
MAR 29 1988

CONSERVATION DIVISION  
WICHITA, KANSAS  
03-29-88

I (and my employees) observe this plugging.

DATE 4-6-88

INV. NO. 20300

Signed Stephen J. Pfeifer  
(TECHNICIAN)