

To: 1 020485 8-1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-22,086 - 00-00138 R
NE NW SE, SEC. 22, T. 29 S, R. 14 W/E
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30128
Operator: Kenneth S. White
Name & Address 200 E. First, Suite 210
Wichita, KS 67202

Lease Name Eads Well # 1
County Pratt
Well Total Depth 4650 151.12 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 5 a.m. Day: 1 Month: 8 Year: 1992

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 750' with 50 sx cement,
2nd plug at 270' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7 a.m. Day: 1 Month: 8 Year: 1992

ACTUAL PLUGGING REPORT 1st plug at 750' with 50 sx cement,
2nd plug at 270' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

DATE 9-24-92
36234

Signed Glenn R. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1992
CONSERVATION DIVISION
Wichita, Kansas