

1 060827

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,769-00-00
SE NW SE, SEC. 21, T 29 S, R 14 W/E
1650 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Lease Name Blanchat Well # 1-21

Operator: Rine Exploration Company
Name & Address: 300 W. Douglas, Suite 645
Wichita, KS 67202

County Pratt 152.26
Well Total Depth 4685 Arbuckle 20' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/8 feet 317

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Big Springs Drilling, Inc. License Number 5381

Address Box 8287; Munger Station., 400 N. Woodlawn, Suite 29, Wichita, KS 67208

Company to plug at: Hour: 4:00 am Day: 9 Month: March Year: 19 86

Plugging proposal received from Darrell Krier

(company name) Big Springs (phone) 316-681-1732

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1963
Anhydrite 805'

1st plug in the Arbuckle with 40 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:30 am Day: 9 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement, 2nd plug at 350' with 50 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
20 sx cement. 5th plug to circulate rat hole with 15 sx cement.

STATE CORPORATION COMMISSION

MAR 20 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE MAR 20 1986

INV. NO. 13032

APR 10 1986

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: February 11, 1986
month day year

API Number 15- 151-21,769-00-00

OPERATOR: License # 5020
Name Rine Exploration Company
Address Ste 645, 300 W Douglas
City/State/Zip Wichita, Kansas 67202
Contact Person M Bradford Rine
Phone 316.262-5418

SE-NW-SE (location) Sec 21 Twp 29 S, Rge 14
1650 Ft North from Southeast Corner of Section
1650 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5381
Name Big Springs Drilling, Inc
City/State Wichita, Kansas 67208

Nearest lease or unit boundary line 990 feet
County Pratt
Lease Name Blanchat Well# 1-21
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 100 feet
Lowest usable water formation Pleistocene
Depth to Bottom of usable water 250 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 315 feet
Conductor pipe if any required none feet
Ground surface elevation 1963 feet MSL
This Authorization Expires 8-5-86
Approved By 2-5-86

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4700 feet
Projected Formation at TD Arbuckle
Expected Producing Formations Simpson

I certify that we will comply with K.S.A. 55-101, at seq., plus eventually plugging hole to K.C.C. specifications.

Date 2/4/86 Signature of Operator or Agent M Bradford Rine Title Partner, geol.
Note in 2-24-86 13 3/8 cond 360' 8 5/8 to 1100' Form C-1 4/84

PUSHER Earl Strickland / Big Springs
TD 4685 FORMATION 10' in Arbuckle
SURFACE PIPE 1 3/8 @ 317 ELEVATION 1963
ANHYDRITE 80
STARTING TIME & DATE 3-9-86
COMPLETION TIME & DATE 6:30 AM
1st PLUG @ 850 FT. W/ 50 SX
2nd PLUG @ 350 FT. W/ 50 SX
3rd PLUG @ 40 FT. W/ 50 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY ΔJ-Titan
TECHNICIAN
Arbuckle 50' in w/ 40 ddy
Bore w/ 50
30' below w/ 50
40-0 SP 10 ddy
oil 15' rat
60/40 w/ 60 gell ✓