

1 070455

10-28-87

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 150'  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,430-0000  
SW SW SE, SEC. 16, T 29 S, R 26 W&E  
555 feet from S section line  
2085 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6044  
Operator: Stelbar Oil Corporation, Inc.  
Name & Address 155 North Market, Suite 500  
Wichita, KS 67202

Lease Name Dodd Well # 1  
County Ford 2/10.28  
Well Total Depth 6470 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1580

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rains & Williamson Oil Company, Inc. License Number 5146  
Address 435 Page Court, 220 West Douglas, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 28 Month: 10 Year: 19 87

Plugging proposal received from Larry Hendalton

(company name) Rains & Williamson Oil Company (phone) 316-265-9686  
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2590'  
Anhydrite 1568-86'

1st plug at 1610' with 50 sx cement, 2nd plug at 800' with 25 sx cement,  
3rd plug at 40-0' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:45 a.m. Day: 28 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1610' with 50 sx cement,  
2nd plug at 800' with 25 sx cement,  
3rd plug at 40-0' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1987  
10-29-87  
CONSERVATION DIVISION  
WICHITA, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-4-87  
INV. NO. 18751

Signed Dan Hoffman  
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date ... October 12 1987

API Number 15- 057-20,430-0000

OPERATOR: License # 6044... 150' SW SW SE 1/4 Sec... 16 Twp. 29S S, Rg. 26W. West Name Stelbar Oil Corporation, Inc. Address 155 N. Market, Suite 500 City/State/Zip Wichita, KS. 67202 Contact Person John C. Shawver Phone (316) 264-8378

CONTRACTOR: License # 5146... Name Rains. & Williamson Oil Co., Inc. City/State Wichita, KS. 67202 Well Drilled For: X Oil, SWD, Gas, Inj, OWWO, Expl Well Class: Infield, Pool Ext., XX Wildcat Type Equipment: X Mud Rotary, Air Rotary, Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

Nearest lease or unit boundary line 555 feet County Ford Lease Name Dodd Well # 1 Ground surface elevation Unknown Feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 250 feet Depth to bottom of usable water 800 feet Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 1520 Conductor pipe required Projected Total Depth 6400 Formation Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 9/24/87 Signature of Operator or Agent John C. Shawver Title Vice-President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 820 feet per Alt. 1 X This Authorization Expires 4-2-88 Approved By RA 10-2-87

ACTIVE DATE: 10-7-87

haul water

Spud 10/10/87 12:00 1520 + 898 80' Cond 16 1/4"

150' SW SW SE 1/4 Sec... 16 Twp. 29S S, Rg. 26W. West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug number, depth, and cement quantity. 1st plug @ 6340 feet depth with 50 sxs of cement. 2nd plug @ 1520 feet depth with 50 sxs of cement. 3rd plug @ 40 feet depth with 10 sxs of cement. 4th plug @ feet depth with sxs of. 5th plug @ feet depth with sxs of. (2) Rathole with 10 sxs (b) Mousehole with sxs

PUSHER Larry Hendalator TD 6470' FORMATION Arbuckle SURFACE PIPE 8 3/8" @ 15-80' ANHYDRITE 1568' ELEVATION 2590' STARTING TIME & DATE 10-28-87 6:00 AM COMPLETION TIME & DATE 9:45 AM 1610 1st PLUG @ 7580 FT. W/ 50 SX 2nd PLUG @ 800 FT. W/ 25 SX 3rd PLUG @ 40-0 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ 5 sxs 60/40 w/ 60/40 Allied CEMENT COMPANY TECHNICIAN D.G.

Arbi 6400'

RECEIVED THE CORPORATION COMMISSION OCT 29 1987 CONSERVATION DIVISION Wichita, Kansas