



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Kirkman of Xplor Drlg.. Co. has this date requested permission to plug the following described well:

Mr. Kirkman guarantees payment of the plugging fee.

Operator's full Name: Xplor Drlg., Co.

Complete Address: 453 S. Webb Rd., Bxo 18611, Wichita, Ks. 67207

Lease Name: Andrews Well No. 4

Location: NE SW SE Sec. 24 Twp 29s Rge. 14 (E)(W) W

County: Pratt Total Depth 4407 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Kirkman was instructed to plug the well as follows:

Pipe pulled on this well 9-20-74. Top never plugged. 495'  
10 3/4" casing. 5 1/2" casing set at 4406'-No information on  
pref's-Sand back to 4200'-Mix & dump 4 sax cement on top  
of sand w/dump bailer. Pull 2286' casing. Dump 8 yard grout  
in casing from 400' back to zero. Pratt Ready Mix.

RECEIVED  
STATE CORPORATION COMMISSION

Very truly yours,

JUL 14 1980  
CONSERVATION DIVISION  
Wichita, Kansas

Conservation Division Agent