

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67201
RECEIVED
SEP 29 1966
9-29-66
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 26, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jim Lahar of B and B Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie

Complete Address: 413 Union Center, Wichita, Kansas

Lease Name: Baker "A" Well No. 1

Location: SW SW SW Sec. 4 Twp. 24 Rge. 5 (E) (W) X

County Reno Total Depth 3880' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and $\frac{1}{2}$ sack hulls to 240' and
cement hole with 30 sacks through drill pipe. Fill hole with mud to
40'. Push plug and $\frac{1}{2}$ sack hulls to 40' and cap hole with 15 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Stuart J. Loren
Conservation Division Agent