

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

October 6, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 16 1970 10-16-70  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Darrel Kelso of Knight Casing Pulling Co., Inc. this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: R. L. Evans

Complete Address: Rural Route, Hutchinson, Kansas 67501

Lease Name: Kincaid Well No. 2

Location: SW NW NE Sec. 21 Twp. 24 Rge. 4 (E)(W) X

County: Reno Total Depth 3371' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Kelso was instructed to plug the well as follows:

Fill hole with sand to 3340' and cement with 5 sacks cement.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and cement

hole with 35 sacks cement. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 15 sacks cement.

Very truly yours,

Conservation Division Agent