

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

August 9, 1963

RECEIVED
 STATE CORPORATION COMMISSION

AUG 19 1963
 8-19-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Elmer Zimmerman of Woodman-Iannitti Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Zimmerman guarantees payment of the plugging fee.

Operator's full Name: Woodman-Iannitti Drilling Co.

Complete Address: 714 Union Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Birkett Well No. 1

Location: NW NE NE Sec. 20 Twp. 24 Rge. 8 (E) (W) X

County Reno Total Depth 4188' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Zimmerman was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 225'. Push
plug and $\frac{1}{4}$ sack hulls to 225' and cement with 20 sacks
through drill pipe. Fill hole with mud to 35'. Push plug
and $\frac{1}{4}$ sack hulls to 35' and cap hole with 10 sacks cement.
Bridge rathole, and cement with 2 sacks.

Very truly yours,

William J. Loren
 Conservation Division Agent