



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

March 3, 1982

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Richard Cox of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Leach and Associates, Inc.

Complete Address: 11237 W. 26th, Lakewood, CO. 80215

Lease Name: Grabbs Well No. 1

Location: C SW SE Sec. 16 Twp. 24 Rge. 8 (E) (W)

County: Reed Total Depth: 4140'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Cox was instructed to plug the well as follows:

8 5/8" - 331-225 sacks. Circulate hole and fill with mud.  
Pump 50 sacks 50/50 Perm mix w/2% gel and 3% c.c. through drill pipe  
at 350'. Fill hole with mud to 40'. Push plug and 1/2 sack  
hulls to 40' and cap hole with 10 sacks cement. Cement  
rathole with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 10 1982  
3-10-82  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

Alberic J. Lomen  
Conservation Division Agent