

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
March 17, 1966

MAR 21 1966
3-21-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. R. B. Mc Farland of Solar Oil Company has this date requested permission to plug the following described well:

Mr. Mc Farland guarantees payment of the plugging fee.

Operator's full Name: Solar Oil Company

Complete Address: 1117 Union Nat'l Bldg., Wichita, Kansas

Lease Name: Fesler Well No. 1

Location: NE NE SE Sec. 18 Twp. 24 Rge. 8 (E) (W) X

County Reno Total Depth 3781' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mc Farland was instructed to plug the well as follows:

Fill hole with mud to 205'. Push plug and 1/3 sack hulls to 205' and
cement hole with 20 sacks through drill pipe. Fill hole with mud to
35'. Push plug and 1/3 sack hulls to 35' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent