

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

APR 1 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Claude Boman of Tomlinson-Kathol Inc. has this

date requested permission to plug the following described well:

Mr. Boman guarantees payment of the plugging fee.

Operator's full Name: Tomlinson-Kathol Inc.

Complete Address: 414 Union Center, Wichita, Kansas

Lease Name: Beck Well No. # 1

Location: C SW NE Sec. 30 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4317 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Boman was instructed to plug the well as follows:

279' of 8 5/8" surface pipe circulated with 225 sacks cement.

Fill hole with mud to 270', 1st cementing plug, 1/4 sack hulls,

cement with 25 sacks. Fill hole to 40' with mud, 2nd cement-

ing plug, 1/4 sack hulls, cement with 15 sacks to base cellar.

Rat hole bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent