

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1963

CONSERVATION DIVISION
Wichita, Kansas

8-20-1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Schuyler of Strata Drilling Inc. has this
date requested permission to plug the following described well:

Mr. Schuyler guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Co. Inc.

Complete Address: 925 Patton Road, Great Bend, Kansas

Lease Name: Boylan "A" Well No. # 1

Location: C SE NW Sec. 30 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4400 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Schuyler was instructed to plug the well as follows:

313' of 8 5/8" surface pipe, cement circulated.
Fill hole with mud to 305', 1st cementing plug, 1/4 sack hulls,
cement with 25 sacks. Fill hole with mud to 40', 2nd cement-
ing plug, 1/4 sack hulls, cement with 15 sacks to base cellar.
Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent