

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-047-10025-00-01

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Oct 15, 1967.

Dear Sir:

Mr. D.B. Pully of Forbes Caseing Pulling Inc. this date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: John Roy Evans

Complete Address: P. O. Box 385 Claflin, Kansas. 67525

Lease Name: C. G. King Well No. #1

Location: SW-SW-SE Sec. 2 Twp. 26 Rge. 18WE (W) W

County Edwards Total Depth 4755' Oil Well Abd.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pully was instructed to plug the well as follows:

299' of 8 5/8" surface pipe circulated with 300 sacks
cement. 4753' of 4 1/2" long string. Top perforation at
4558'. Sand to 4525' & 4 sacks cement. Mud to 280', 10'
rock bridge, 5 sacks cement ^{as} overnite bridge, bailed down, &
20 sacks cement. Mud to 40', 10' bridge & 10 sacks cement
to surface.

Very truly yours,

Herman Justus
Conservation Division Agent