

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-047-00134-00-01

RECEIVED
STATE CORPORATION COMMISSION

FEB 2 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 1, 1967

Dear Sir:

Mr. Herman Johnson of Gabbert-Jones, Inc. has this date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Glenn N. Rupe

Complete Address: 222 Brown Bldg., Wichita, Kansas

Lease Name: Newsom "A" Well No. # 1

Location: C S/2 NE SE Sec 11 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 3528' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

328' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 280', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent