

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-10117-00-01  
Spot: NWSWSW Sec/Twnshp/Rge: 2-21S-14W  
990 feet from S Section Line, 300 feet from W Section Line  
Lease Name: BIRBECK Well #: 2  
County: STAFFORD Total Vertical Depth: 3645 feet

Operator License No.: 5088  
Op Name: DARRAH, JOHN JAY, JR.  
Address: P.O. BOX 2786  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3480		WITH 2 SX CMT
PROD	4.5	3639	0	WITH 150 SX CMT
SURF	8.625	270		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/21/2015 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 3480' & 2 SX CMT. PERFORATE AT 750'. RUN TBG IN TO 750'. PUMP DOWN TBG WITH CMT. CIRCULATING CMT TO SURFACE INSIDE CASING/OH & SURFACE PIPE ANNULUS TO SURFACE & ALSO FILLING 4 1/2" CASING TO SURFACE WITH CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/05/2015 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3480' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 4 1/2" AT 750'. RUN TBG IN TO 750'. PUMPED DOWN 2 3/8" TBG WITH 150 SX CMT. LOST RETURNS. WELL ON VACUUM. SHUT DOWN. LET CMT SET 3 HOURS. CMT NOT SET WELL ENOUGH SDON. 9/22/15: TAG TOC @ 195'. PERFORATE AT 190'. PUMPED DOWN 2 3/8" TBG WITH 50 SX CMT CIRCULATING CMT TO SURFACE INSIDE TBG/CSG ANNULUS. SHUT IN TBG/CSG ANNULUS. PUMPED INTO PERFS IN 4 1/2" CASING AT 190' AT 1/4 TO 1/2 BPM AT 300#-500# WITH VERY SLIGHT INDICATION OF BLOW & TRICKLE OF RETURNS UP CSG/SURFACE PIPE ANNULUS. 10/5/15: RUN 1" DOWN 8 5/8" X 4 1/2" ANNULUS. TAGGED TOC @ 60'. PUMPED DOWN 1" WITH 15 SX CMT CIRCULATING CMT TO SURFACE. RUN 1" INSIDE 4 1/2" CASING. TAG TOC @ 20'. PUMPED DOWN 1" WITH 5 SX CMT FILLING 4 1/2" CASING TO SURFACE WITH CMT.

Perfs:

Top	Bot	Thru	Comments
3579	3584		
3528	3532		

KCC WICHITA  
OCT 20 2015  
RECEIVED

10-20-15

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

10/27/15 CKM

District: 01

RECEIVED  
OCT - 9 2015  
KCC DODGE CITY

Signed Stephen J. Pfeifer  
(TECHNICIAN)