

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20912-00-00
Spot: W2NENENE Sec/Twnshp/Rge: 1-9S-23W
4950 feet from S Section Line, 610 feet from E Section Line
Lease Name: CASEY JONES Well #: 4(1-4)
County: GRAHAM Total Vertical Depth: 3840 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3839		128 SX
SURF	8.625	128		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2015 3:00 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORP Phone: (620) 282-9034

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement, 600 # hulls.
Perforations at 3571' - 3581', 3584' - 3806'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2015 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 1100', 1925', 2500'.
Ran tubing to 3709' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2993' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2126' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1195' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 50 sx cement. Tied on to backside and squeezed with 100 sx cement and 300 # hulls. Shut in pressure 100 psi.

GPS: 39.30589 -099.83073

Perfs:

Top	Bot	Thru	Comments
3622	3624		
3584	3806		
3571	3581		

KCC WICHITA
OCT 26 2015
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2509

Plugged through: TBG

District: 04

Signed _____

[Signature]
(TECHNICIAN)

CM

10/27/15 ckm

OCT 01 2015