

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-23737-00-00  
Spot: S2SWSE Sec/Twnshp/Rge: 12-24S-14W  
335 feet from S Section Line, 2030 feet from E Section Line  
Lease Name: RIXON Well #: 1-12  
County: STAFFORD Total Vertical Depth: 4223 feet

Operator License No.: 34434  
Op Name: EDISON OPERATING COMPANY LLC  
Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3672		WITH 2 SX CMT
CIBP		3890		WITH 2 SX CMT
PROD	5.5	4222	1596	WITH 125 SX CMT
SURF	8.625	408		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2015 12:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 3890' & 3670' WITH 2 SX CMT ON TOP OF EACH CIBP. PLUG AT 850' WITH 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/12/2015 3:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP'S AT 3890' & 3672'. PUT 2 SX CMT ON TOP OF EACH CIBP THROUGH DUMP BAILER. 1ST PLUG AT 848' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 421' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3936	3972		
0			

KCC WICHITA  
OCT 20 2015  
RECEIVED  
10-20-15

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

10/27/15CKM  
  
(TECHNICIAN)

RECEIVED  
OCT 14 2015  
KCC DODGE CITY