

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23775-00-00
Spot: NWSENW Sec/Twnshp/Rge: 36-22S-14W
3644 feet from S Section Line, 3716 feet from E Section Line
Lease Name: BARTLETT Well #: 1-36
County: STAFFORD Total Vertical Depth: 3847 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3530		WITH 2 SX CMT
CIBP		3700		WITH 2 SX CMT
PROD	5.5	3847	1516	WITH 125 SX CMT
SURF	8.625	292		WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2015 1:30 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 3700' & 2 SX CMT. CIBP @ 3530' & 2 SX CMT. PLUG AT 850' WITH 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2015 3:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 3700' WITH 2 SX CMT. SET CIBP @ 3530' WITH 2 SX CMT. 1ST PLUG AT 830' WITH 50 SX CMT. 2ND PLUG AT 344' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3754	3785		

KCC WICHITA
OCT 20 2015
RECEIVED
10-20-15

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

10/27/15 ckm

District: 01

Signed Larry Dideris ECRS
(TECHNICIAN)

RECEIVED
OCT 16 2015
KCC DODGE CITY